

LEASE NAME Kinzie

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #3

3630 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 23 TWP. 29 RGE. 13 (E) or (W)

COUNTY Pratt

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS Box 352, Russell, Ks. 67665

PHONE# 913-483-3144 OPERATORS LICENSE NO. 5135

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed _____

Plugging Commenced 10-1-90

Plugging Completed 10-22-90

The plugging proposal was approved on October 4, 1990 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom T.D. 4707'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10-3/4"	208'	None
				5-1/2"	4700'	2,441.32'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet, each set. Dumped sand to 4600' and 5 sacks cement. Shot casing at 4021', 3621', 3219', 3004', 2812', 2812', 2620', & 2433'. Pulled 74 joints of 5-1/2" casing. Allied plugged well with 300# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, and 125 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 150 psi and shutin 100 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.


STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 25th day of October, 1990



Iona M. Leatherman
 Notary Public

My Commission Expires:

John O. Farmer, Inc. -

Kinzie #3
NE SW NW Sec. 23-29S-13W
Pratt County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
301 S. Broadway
Wichita, Kansas 67202

Commenced: April 26, 1975
Completed: May 14, 1975

Drillers Log

Sand	190
Shale	212
Shale & Shells	576
Shale	1634
Shale & Lime	2050
Lime & Shale	2440
Shale & Lime	2845
Lime & Shale	3215
Shale & Lime	3470
Lime & Shale	3845
Shale & Lime	3985
Lime	4155
Lime & Shale	4265
Lime	4707 RTD

RECEIVED
STATE CORPORATION COMMISSION

SEP 27 1977

Wichita, Kansas