

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,437-50-50

LEASE NAME Kinzie

WELL NUMBER A#2

 Ft. from S Section Lin.

 Ft. from E Section Lin.

SEC. 23 TWP. 29 RGE. 13 XX or (W)

COUNTY Pratt

Date Well Completed

Plugging Commenced 5-14-92

Plugging Completed 10:00 AM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Tri-J Tubulars, Inc.

ADDRESS 125 N. Market, St 1532, Wichita, Ks 67202

PHONE# (316) 264-1144 OPERATORS LICENSE NO. 30208

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-14-92 (date)

by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, Is well log attached?

Producing Formation Depth to Top 4196 Bottom 4202 T.D. 4782

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	250	0
				5 1/2	4745	2532

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other p were used, state the character of same and depth placed, from feet to feet each: Bottom plug: Sanded to 4140 & bailed 5 sx cement.

Top plug: Pumped 300 lbs Hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs Hulls 8 5/8 wiper plug, 100 sx 60/40 6% gel. Had max pressure of 200 lbs & shut in of 150 lbs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Tri-J Tubulars, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Gary G. Burke

(Employee of Operator) or (Operator

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Gary G. Burke Pres

(Address) Box 251, Great Bend, Kansas 67530

AND SWORN TO before me this 14 day of May

Anna K. Burke
Notary Public

My Commission Expires: 4-30-96

