


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Kiowa County. Sec. 6 Twp. 27S Rge. 17W-E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_  
C-SE SE NE/4  
Lease Owner Bold Oil Co. and Paul Condit, Individual  
Lease Name Fatzer Well No. 2  
Office Address P. O. Box 48, Fellsburg, KS 67048  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above  
Section Plot

Dry Hole  
Date Well completed November 8, 1980  
Application for plugging filed Verbal Application 1980  
Application for plugging approved Verbal Approval 1980  
Plugging commenced November 8, 1980  
Plugging completed November 8, 1980  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 1980

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,805'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	420'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,805 ft. (rotary total depth) to 420 ft. Set plug at 420 ft. and cemented with 60 sacks cement. Filled hole with heavy rotary mud from 420 ft. to 30 ft. Set solid plug at 30 ft. and cemented to cellar with 10 sacks cement, 10 sacks cement in rat-hole.

Plugging operations accomplished utilizing Halliburton Services Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services  
410 Union Center Bldg., Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick

Dean Britting, Agent

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting

251 N. Water - Suite 10, Wichita, KS 67203  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of November, 1980

Elsie Willison  
Elsie Willison - Notary Public.

My commission expires July 25, 1982

RECEIVED  
CONSERVATION DIVISION  
STATE CORPORATION COMMISSION  
NOV 19 1980

