

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-097-29717-0000

LEASE NAME Butler-Thompson

WELL NUMBER 2-24

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 24 TWP. 27 RGE. 16 (E) or (W)

COUNTY Kiowa

Date Well Completed 2-18-81

Plugging Commenced 12-8-99

Plugging Completed 12-10-99

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Vincent Oil Corporation

ADDRESS 125 N. Market, Suite 1075, Wichita, KS 67202

PHONE# (316) 262-3573 OPERATORS LICENSE NO. 5004

Character of Well oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-8-99 (date)

by Dodge City, KS (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? _____

Producing Formation Lansing-Kansas City Depth to Top 4042 Bottom 4445 T.D. 4589
& Marmaton

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		3370		8 5/8	372	0
				5 1/2	4603	2600

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Sanded to 4362'. Bailed 5 sks of Portland. Shot 2641. Worked pipe free/ Pulled to 1100' Pumped 7 gal 50 sks 3 gal. Pulled to 400'. Pumped 50 sks. Pulled to 40'. Pumped 10 sks. Lay last point down. Well stayed full.

Name of Plugging Contractor QWS License No. 31925

Address 415 E. Main, Sterling, KS 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vincent Oil Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Richard A. Hiebsch

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Richard A. Hiebsch

Richard A. Hiebsch

(Address) 125 N. Market, Suite 1075, Wichita, KS

67202

YOLANDA EUBANKS
NOTARY PUBLIC
STATE OF KANSAS

My Com. Exp. 10-9-2001
RECEIVED

STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 5th day of January, 2000

Yolanda Eubank
Notary Public Yolanda Eubanks

Form CP-4
Revised 05-88

JAN 06 2000

My Commission Expires: 10-9-2001

ALLIED CEMENTING CO., INC.

2229

Federal Tax I.D.# 48-0727860

REMIT TO: P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

MEDICINE LODGE

DATE <u>12-10-99</u>	SEC. <u>24</u>	TWP. <u>27 1/2</u>	RANGE <u>16W</u>	CALLED OUT <u>12:00 PM</u>	ON LOCATION <u>2:00 PM</u>	JOB START <u>3:15 PM</u>	JOB FINISH <u>5:00 PM</u>
LEASE <u>NEWSON</u>		WELL # <u>29-24</u>	LOCATION <u>FRONT/KIOWA Co. LINE ON ST</u>		COUNTY <u>KIOWA</u>	STATE <u>KANSAS</u>	
OLD OR NEW (Circle one) <u>OLD</u>			<u>4 3/4" , WIS</u>				

CONTRACTOR QUALITY Well Svc.

TYPE OF JOB OLD HOLE PLUG

HOLE SIZE 7 7/8" T.D.

CASING SIZE 8 7/8" DEPTH 372'

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER VINCENT OIL CORP.

CEMENT AMOUNT ORDERED 105 cu

120 x 60 x 40 = 6

COMMON A	<u>72</u>	@	<u>6.35</u>	<u>457.20</u>
POZMIX	<u>48</u>	@	<u>3.25</u>	<u>156.00</u>
GEL	<u>16</u>	@	<u>9.50</u>	<u>152.00</u>
CHLORIDE		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>120</u>	@	<u>1.05</u>	<u>126.00</u>
MILEAGE	<u>120 x 20</u>		<u>.04</u>	<u>100.00</u>
TOTAL				<u>\$ 991.20</u>

EQUIPMENT

PUMP TRUCK # 312 CEMENTER _____ HELPER KEVIN BUNSBADT

BULK TRUCK # 312 DRIVER BLAINE BARR

BULK TRUCK # _____ DRIVER _____

REMARKS:

LOAD HOLE WITH 7 x COILED WATER

SPOT 50% @ 1100' - DISPLACE WITH

18 BBLs COILED WATER

LOAD HOLE - SPOT 50% @ 400'

LOAD HOLE + CALCULATE CEMENT

TO SURFACE FROM 40'

10% FOR WATER WELL

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE 450.00

EXTRA FOOTAGE @ _____

MILEAGE 20 @ 2.85 57.00

PLUG @ _____

@ _____

@ _____

TOTAL \$ 507.00

CHARGE TO: VINCENT OIL CORP

STREET 125 N. MARKET, # 1075

CITY WICHITA STATE KANSAS ZIP 67202

FLOAT EQUIPMENT

@ _____

@ _____

@ _____

@ _____

@ _____

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TOTAL _____

TAX 95.88

TOTAL CHARGE 1594.08

DISCOUNT 100.00 IF PAID IN 30 DAYS

SIGNATURE Joseph E. Mies

PRINTED NAME _____

SIGNATURE Joseph E. Mies

RECEIVED
STATE CORPORATION COMMISSION

JAN 06 2000

CONSERVATION DIVISION
Wichita, Kansas