

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-097-20653-0000
LEASE NAME Butler-Thompson
WELL NUMBER 1-24
4260 Ft. from S Section Line
660 Ft. from E Section Line
SEC. 24 TWP. 27S RGE. 16 (E) or (W)
COUNTY Kiowa

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Vincent Oil Corporation
ADDRESS 125 N. Market, Suite 1075, Wichita, KS 67202-1721
PHONE (316) 262-3573 OPERATORS LICENSE NO. 5004

Date Well Completed 8-11-80
Plugging Commenced 12-7-99
Plugging Completed 12-8-99

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-7-99 (date)
by Dodge City, KS (KCC District Agent's Name).

Is ACC-1 filed? yes If not, is well log attached? _____

Producing Formation Marmaton Depth to Top 4398 Bottom 4458 T.D. 4610

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	371	0
				4 1/2	4608	2410

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set
Sanded bottom to 4382'. Bailed 4 sks Portland Shot 2410. Pulled to 1100'. Pumped 10. Gels with 50 sks. Pulled to 400'. Pumped 50 sks. Pulled to 40'. Pumped 10 sks. Hole stayed full. Lay last unit down.

Name of Plugging Contractor QWS License No. 31925


Address 415 E. Main, Sterling, KS 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vincent Oil Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Richard A. Hiebsch (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Richard A. Hiebsch
Richard A. Hiebsch, President
(Address) 125 N. Market, Suite 1075, Wichita, KS 67202



AND SWORN TO before me this 5th day of January, 2000

RECEIVED
STATE CORPORATION COMMISSION

My Commission Expires: 10-9-2001

JAN 06 2000

CONSERVATION DIVISION
Wichita, Kansas

ALLIED CEMENTING CO., INC.

2199

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Medicine Lodge

DATE <i>12-08-89</i>	SEC. <i>24</i>	TWP. <i>27</i>	RANGE <i>16</i>	CALLED OUT <i>1:00 pm</i>	ON LOCATION <i>2:30 pm</i>	JOB START <i>3:00 pm</i>	JOB FINISH <i>4:30 pm</i>
LEASE <i>Johnson</i>	WELL # <i>124</i>	LOCATION <i>Pratt West to Coline</i>		COUNTY <i>Nowa</i>	STATE <i>KS.</i>		

OLD NEW (Circle one)

CONTRACTOR *Quality well service*

TYPE OF JOB *OHP*

HOLE SIZE *8 3/8 34" I.D.*

CASING SIZE *4 1/2* DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX *100* MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER *Vincent oil Corp*

CEMENT

AMOUNT ORDERED *110 sx 60:40:6*

10 sx Gel

COMMON	<i>66</i>	@	<i>6.35</i>	<i>419.10</i>
POZMIX	<i>44</i>	@	<i>3.25</i>	<i>143.00</i>
GEL	<i>16</i>	@	<i>9.50</i>	<i>152.00</i>
CHLORIDE		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<i>110</i>	@	<i>1.05</i>	<i>115.50</i>
MILEAGE	<i>110 x 20</i>		<i>-.04</i>	<i>100.00</i>

TOTAL \$ *929.60*

EQUIPMENT

PUMP TRUCK CEMENTER *Carl Balding*

352 HELPER *Stine winson*

BULK TRUCK

242 DRIVER *David west*

BULK TRUCK

_____ DRIVER _____

REMARKS:

1st plug 1100' Load Hole with 5sx Gel water, pump 50sx 60:40:6. Displace with 5sx gel water.

2nd plug 400' Load Hole w/ Freshwater pump 50 sx 60:40:6 Displace with freshwater

3rd plug 40' circulate cement to surfcks with 10 sx 60:40:6

SERVICE

DEPTH OF JOB *1100'*

PUMP TRUCK CHARGE _____ *750.00*

EXTRA FOOTAGE _____ @ _____

MILEAGE *20* @ *2.85* *57.00*

PLUG _____ @ _____

_____ @ _____

TOTAL \$ *507.00*

CHARGE TO: *Vincent oil Corp*

STREET *135 N. MARKET #1075*

CITY *WICHITA* STATE *KANSAS* ZIP *67202*

FLOAT EQUIPMENT

	@		
	@		
	@		
	@		
	@		

To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE *Richard O. McIntyre*

TAX *91.94*

TOTAL CHARGE *1528.54*

DISCOUNT *287.32* IF PAID IN 30 DAYS

NET # *1241.22*

Richard O. McIntyre

PRINTED NAME RECEIVED

STATE CORPORATION COMMISSION

IAN 06 2000

CONSERVATION DIVISION
Wichita, Kansas