

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-20658-0000

LEASE NAME Burtsfield

WELL NUMBER 3-19

 Ft. from S Section Lin

 Ft. from E Section Lin

SEC. 19 TWP. 27 RGE. 16 ~~XXX~~or (W

COUNTY Kiowa

Date Well Completed

Plugging Commenced 4-17-92

Plugging Completed 11:15 AM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Farrar Pump & Supply Co. Inc.

ADDRESS P.O. Box 209, Medicine Lodge, Kansas 67104

PHONE# (316)886-3763 OPERATORS LICENSE NO. 3399

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-17-92 (date)

by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filled? Yes If not, Is well log attached?

Producing Formation Lansing Depth to Top 4111 Bottom 4117 T.O. 4680

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	407	0
				4 1/2	4671	2200

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s Pumped into 8 5/8 a total of 300 lbs Huls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs Huls, 8 5/8 wiper plug, 120 sx cement - 60/40 6% gel. Had max pressure of 500 lbs & shut in pressure of 250 lbs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No.

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Farrar Pump & Supply Co. Inc.

STATE OF Kansas COUNTY OF Barton, ss.


Anna K. Burke

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fac statements, and matters herein contained and the log of the above-described well as filed i the same are true and correct, so help me God.

(Signature) Anna K. Burke

(Address) Box 251, Great Bend, Kansas 67530



SUBSCRIBED AND SWORN TO before me this 20 day of April, 19 92

Gary G. Burke
Notary Public

My Commission Expires: 4-30-93

STATE CORPORATION COMMISSION
RECEIVED
APR 21 4-21-92
INFORMATION DIVISION
Wichita, Kansas