

15163-01874-00-00  
10-8

259  
R

6-031592

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- \_\_\_\_\_  
NW SW SE /4 SEC. 22, 10 S, 18 W  
990 feet from S section line  
2310 feet from E section line

Operator license# 4335 Lease Shepard "I" well # 1

Operator: Terrol Energy, Inc. County Rooks

Address: 3245 Broadway Well total depth 3540 feet <sup>115.05</sup>  
Boulder, Colorado 80302 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 165 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 8 Month: October Year: 91

Plugging proposal received from: Terry Enright

Company: Terrol Energy, Inc. Phone: \_\_\_\_\_

Were: 8 5/8" set @ 165' w/125 sx. cwc. 4 1/2" set @ 3640' w/250 sx.  
D.V. tool set @ 1440' w/675 sx. cwc. Order 225 sx. 65/35 poz. 10% gel.  
500# hulls. B.J. Services Cement Company.

Hole open across perf's.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All , Part , None

Completed: Hour: 10:30A.M., Day: 8, Month: October, Year: 91

Actual plugging report: Squeezed 4 1/2" casing w/225 sx. cement blend  
w/500# hulls mixed in from 3640' to surface to max. P.S.I. 500#  
Close in P.S.I. 500#.  
Tested 8 5/8 annulus to max. P.S.I. 500#. Cement @ surface, would  
not take fluid.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 4 1991

Remarks: \_\_\_\_\_

CONSERVATION DIVISION  
WICHITA, KANSAS

I did  or did not  observe the plugging.

Carl Goodrow

**INVOICED**

DATE 12-5-91

INV. NO. 33950

File G

(agent)  
Form CP-2/3