

1 080285

15.151-20256-00-00

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION E/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Not available
NE/4, SEC. 27, T 29 S, R 13 W/X
3960 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name Henry Well # 2

Operator: John O. Farmer
Name & Address 370 West Wichita
Russell, KS 67665

County Pratt 151.13
Well Total Depth 4650 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 12-3/4 feet 200 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor John O. Farmer License Number 5135

Address 370 West Wichita, Russell, KS 67665

Company to plug at: Hour: 9:00 am Day: 17 Month: December Year: 19 84

Plugging proposal received from Alex Dreher

(company name) John O. Farmer (phone) 913-483-3144

were: Did not ever run pipe. Well has been on T/A list since 1974. Lost circulation at 712' No recovery

12-17-84 Ran tubing to 750' and pumped 2 sx hulls, 20 sx gel and 100 sx cement. Well on vacuum.

12-18-84 Ran tubing to 550' and pumped 300 gal. Flow Check and 230 sx 1/2# Flow seal

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 am Day: 21 Month: December Year: 19 84

ACTUAL PLUGGING REPORT

cement. Did not circulate.

12-19-84 Tagged cement at 589' and pumped 230 sx cement 1/2# Flow Seal

12-21-84 Tagged cement at 124' Filled hole with 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
01-02-85
JAN 02 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 3% cc by Halliburton. No recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If not observed, observe this plugging.)

DATE 1-14-85
INV. NO. 6413

Signed J. A. Metz (TECHNICIAN)