

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21250-00-00
Spot: CSENWNW Sec/Twnshp/Rge: 25-29S-13W
990 feet from N Section Line, 990 feet from W Section Line
Lease/Unit Name: COMBS Well Number: 1
County: PRATT Total Vertical Depth: 4725 feet

Operator License No.: 5420
Op Name: WHITE & ELLIS DRILLING, INC.
Address: PO BOX 48848
WICHITA, KS 67201

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 407 WITH 300 SX CMT
Production: Size 4.5 feet: 4726 WITH 165 SX CMT
Liner: Size _____ feet:

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/21/2001 12:45 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SAND TO 3880' & 4 SX CMT. 1ST PLUG AT 760' WITH 50 SX CMT. 2ND PLUG AT 430' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. USE 10 SX GEL FOR GEL SPACER.

153-56

Plugging Proposal Received By: STEVE PFEIFER
Date/Time Plugging Completed: 03/21/2001 1:45 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4650'. CIBP @ 4145'. PERFS AT 3931-38'. SANDED BACK TO 3880' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2' CASING. 1ST PLUG AT 760' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 430' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

INVOICED
DATE 4-6-01
INV. NO. 2001061592

RECEIVED
STATE CORPORATION COMMISSION
APR - 5 2001
CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2600' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

MAR 29 2001

Form 18-2/3

AP