

1 010270

7-21-87 -00-01

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-21,571-A  
Approx.  
SW SW SW, SEC. 24, T 29 S, R 13 W/E  
330 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9854

Lease Name Flora Well # 1-24

Operator: MarMac Petroleum Company  
Name & Address 1026 Union Center Bldg.  
Wichita, KS 67202

County Pratt 153.24

Well Total Depth 4715 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 429

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 2:45 p.m. Day: 21 Month: 7 Year: 19 87

Plugging proposal received from Douglas McGinness

(company name) MarMac Petroleum Company (phone) 316-267-6065

were: 5 1/2" at 4714' PBTD 4225' Perfs at 3936-38' Elevation 1887'GL

1st plug sand back to 3875' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 2'sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, release 8 5/8" wiper plug and pump 130 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:20 p.m. Day: 21 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3875' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, 8 5/8" wiper plug and pumped 130 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Cement dropped 97' - was filled in with Ready Mix on 7/23/87.

JUL 24 1987

Maximum pressure 600 psi and shut in 300 psi.

CONSERVATION DIVISION  
Wichita Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1903' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

Signed Jack Luthi  
(TECHNICIAN)

DATE 7-24-87

INV. NO. 17620

7-21