

10-22

To: 1 040474
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-20,283 -00-00

NE SW NW, SEC. 23, T 29 S, R 13 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

3630 feet from S section line

4290 feet from E section line

Operator: John O. Farmer, Inc.

Lease Name Kinzie Well # 3

Name & Address Box 352

County Pratt 152.97

Russell, KS 67665

Well Total Depth 4707 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 208

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 12 p.m. Day: 22 Month: 10 Year: 19 90

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

was: 5 1/2" at 4700', Open hole 4700-07'

1st plug sand back to 4650' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:45 p.m. Day: 22 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4650' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 125 sx cement.

Maximum pressure 150 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2441' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 10-5-90
INV. NO. 29822

001 30 1990
10-30-90
CONSERVATION DIVISION
Wichita, Kansas

Signed Steve Pfeifer
(TECHNICIAN)