

9-16

✓ 858

1 040566

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,235 - ~~00-00~~

NE NW SW, SEC. 23, T. 29 S, R. 13 W/E

2310 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name Kinzie Well # 1

Operator: John O. Farmer, Inc.

County Pratt 153.14

Name & Address P.O. Box 352

Well Total Depth 4712 feet

Russell, KS 67665

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10 3/4 feet 226

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 16 Month: 9 Year: 19 91

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 4689' w/150 sx cement, Perfs at 4382-92'(top perf.)

1st plug sand back to 4330' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 10 3/4"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Case Morris  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45 a.m. Day: 16 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4330' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 40 sx cement, 10 sx gel, 100 lbs. hulls, and 110 sx cement.

Maximum pressure 400 psi and shut in 150 psi.

SEP 20 1991

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2023.16' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED (void) observe this plugging.

DATE 9-27-91

Signed Steph... (TECHNICIAN)

INV. NO. 33233