

To: ✓ 040660 S-14
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,172-00-00 106
NW NW SE, SEC. 23, T. 29 S, R 13 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 30208
Operator: Tri-J Tubulars, Inc.
Name &
Address 125 N. Market, Suite 1532
Wichita, KS 67202

2310 feet from S section line
2310 feet from E section line
Lease Name Kinzie Well # 1A
County Pratt 154.24
Well Total Depth 4746 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 248

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 11:30 a.m. Day: 14 Month: 5 Year: 1992

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

work: 4 1/2" at 4568' w/75 sx cement, PBSD 4470', Perfs at 4397-4406'
1st plug sand back to 4340' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:15 p.m. Day: 14 Month: 5 Year: 1992

ACTUAL PLUGGING REPORT 1st plug sanded back to 4340' and dumped 4 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10
sx gel, 100 lbs. hulls, and 100 sx cement.
Maximum pressure 400 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2427' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (and my company) observe this plugging.

DATE 5-22-92

INV. NO. 35323

Signed Stephen J. P. Pappas
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1992
CONSERVATION DIVISION
Wichita, Kansas