

To: 1040659 5-14
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,437 - 00-00 105
S/2 SE SE, SEC. 23, T. 29 S, R 13 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 30208

Operator: Tri-J Tubulars, Inc.
Name & Address 125 N. Market, Suite 1532
Wichita, KS 67202

330 feet from S section line

660 feet from E section line

Lease Name Kinzie Well # 2A

County Pratt 155.41

Well Total Depth 4782 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well _____ Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 9:15 a.m. Day: 14 Month: 5 Year: 19 92

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4745' w/300 sx cement, PBTD 4230', Perfs at 4196-4202'

1st plug sand back to 4140' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10 a.m. Day: 14 Month: 5 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4140' and dumped 5 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 200 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2526' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 5-22-92

INV. NO. 35322

Signed Steve Middleton
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1992
CONSERVATION DIVISION
WICHITA, KANSAS