

1 050464

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,107-0000  
C NE SW, SEC. 29, T 27 S, R 18 W/E

1980 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5118

Lease Name Rosenberger Well # 1

Operator: TGT Petroleum Corp.  
Name &  
Address 209 E. William  
Wichita, KS 67202

County Kiowa 161.85

Well Total Depth 4980 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 434 ✓

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 6:00 pm Day: 28 Month: February Year: 19 85

Plugging proposal received from Harvey Moore

(company name) Abercrombie (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1170' with 50 sx cement

2nd plug at 480' with 40 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9:00 pm Day: 28 Month: February Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1170' with 50 sx cement, 2nd plug at 480' with 40

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to

circulate mouse hole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 11 1985  
3-11-85

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

CONSERVATION DIVISION  
Wichita, Kansas

If additional description is necessary, use BACK of this form.)

(OR) did not observe this plugging.

INVOICED  
DATE 3-12-85

Signed Richard W. Lacey  
(TECHNICIAN)

INVT NO. 7327  
2-28 MAR 26 1985