

1030158

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-20,441-0000

SE NE NW, SEC. 23, T 27 S, R 18 (W/E)

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Livengood Well # 1

Operator: Oil Producers, Inc. of Kansas
Name & Address

County Kiowa

P. O. Box 8647

Well Total Depth 4790 155.68 feet

Wichita, KS 67208

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 390

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 18 Month: April Year: 19 84

Plugging proposal received from Bob Brenneman

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2 set at 4789' PBD 4780' Perfs 4722 - 30

1st plug sand back to 4675' and dump 4 sx cement on top of sand

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump an additional 150 sx cement.

Maximum pressure 1200# and shut in pressure 250#.

Plugging Proposal Received by Steve Bennett
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00 pm Day: 18 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4789' PBD 4780' Perfs 4722-30'

1st plug sand back to 4675' and dump 4 sx cement on top of sand, 2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and release 8 5/8" rubber plug, and pump an additional 150 sx cement.

Maximum pressure 1200# and shut in pressure 250#

Remarks: They recovered 3012' of 4 1/2" casing. Use 60/40 Pozmix 2% gel 3% cc by Allied
(If additional description is necessary, use BACK of this form.)

INVOICED RECEIVED
STATE CORPORATION COMMISSION

DATE 4-20-84

APR 20 1984

Signed Steve Bennett
(TECHNICIAN)

INV. NO. 1197 2-18

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84