

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20586-00-00
Spot: CNENE Sec/Twnshp/Rge: 11-27S-18W
4620 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: RICH Well Number: 1
County: KIOWA Total Vertical Depth: 4720 feet

Operator License No.: 31929
Operator Name: T.T. PRODUCTION, INC.
Address: RR 1, BOX 91
HAVILAND, KS 67059

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 412 WITH 300 SX CMT
Production: Size 4.5 feet: 4719 WITH 200 SX CMT
Liner: Size _____ feet: 153.40

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/21/2000 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SAND BACK TO 4100' & 4 SX CMT. 1ST PLUG AT 1150' WITH 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/21/2000 12:15 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PERFS AT 4651-54, 4616-20, 4602-10. CIBP @ 4220. PERFS AT 4162-73, 4292-4300. SAND BACK TO 4100 & 4 SX CMT ON TOP. 1ST PLUG AT 1172' WITH 50 SX CMT. 2ND PLUG AT 450' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 15 SX CMT. GOOD CIRCULATION THROUGHOUT JOB.

RECEIVED
STATE CORPORATION COMMISSION
NOV 27 2000

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2530' OF 4 1/2" CASING.

Plugged through: CSG

CONSERVATION DIVISION
Wichita, Kansas

District: 01

Signed _____ (TECHNICIAN)

INVOICED

DATE 11/28/00 NOV 22 2000

WV. NO. 2001061021 AP

Form 402/3