

2-4-88

To: 1 051006  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,487-0000  
C SE NW, SEC. 1, T 27 S, R 18 W/E  
3300 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 6033  
Operator: Murfin Drilling Company  
Name & Address 250 North Water, Suite 300  
Wichita, KS 67202

Lease Name Haney Well # 2-1  
County Kiowa 152.46  
Well Total Depth 4691 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 507

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2:30 p.m. Day: 4 Month: 2 Year: 19 88

Plugging proposal received from Mark McCabe

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4738' Perfs at 4634-40'

1st plug sand back to 4580' and dump 4 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" with 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:30 p.m. Day: 4 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4580' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

released 8 5/8" wiper plug and pumped 125 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 09 1988

Maximum pressure 300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

DATE 2-10-88

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 19810