

1041368

TO: STATE CORPORATION COMMISSION

API NUMBER NA
SW SW NE SEC. 25, T 27 S, R 11 W

15-151-19002 00-00

9-23

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME CUNNINGHAM "B" UNIT WELL # 24

TECHNICIAN'S PLUGGING REPORT

COUNTY PRATT

OPERATOR LICENSE # 3880

WELL TOTAL DEPTH 3461 *112.48* FEET

OPERATOR: K.C. RESOURCES, INC. PRODUCTION CSG: SIZE 8 5/8" @ 3414' WITH 500 SX

NAME AND PO BOX 1118 SURFACE CASING: SIZE 13" @ 327' WITH SX

ADDRESS CARDIFF, CA 92007

INVOICED

DATE 10-15-99
SWD WELL D/A
WELL NO. 60693

ABANDONED OIL WELL GAS WELL INPUT WELL

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR PRATT WELL SERVICE, INC LICENSE NUMBER 5893

ADDRESS PO BOX 847, PRATT, KS 67124

COMPANY TO PLUG AT: HOUR: 2:45 PM DAY: 23 MONTH: 09 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM ROD HOVLAND W/K.C. RESOURCES

(COMPANY NAME) PRATT WELL SERVICE (PHONE) 316-672-2531

WERE: OPEN HOLE AT 3424-3461 JUNK IN HOLE=120-3/4" SUCKER RODS AND 10 JOINTS OF 2 3/8" TUBING

1ST PLUG SPOT 50 SX CEMENT AND 200# HULLS AT 2630' INSIDE OF 8 5/8" CASING THROUGH 2 3/8"

TUBING. SPOT PLUGS THROUGH TUBING INSIDE OF 8 5/8". 2ND PLUG AT 600' WITH 50 SX CEMENT.

3RD PLUG AT 300' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT. 5TH PLUG PUMP

DOWN 8 5/8" X 13" ANNULUS WITH 100 SX CEMENT. MAXIMUM PRESSURE AT 500#. SHUT IN WITH 200#.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 23 MONTH: 09 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SPOTTED 50 SX CEMENT & 200# HULLS AT 2630' INSIDE OF 8 5/8" THROUGH 2 3/8" TUBING.

SPOT PLUGS THROUGH TUBING INSIDE OF 8 5/8" CASING. 2ND PLUG AT 600' WITH 50 SX CEMENT.

3RD PLUG AT 300' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT. 5TH PLUG PUMP DOWN

8 5/8" X 13" ANNULUS WITH 100 SX CEMENT. MAXIMUM PRESSURE AT 500#. SHUT IN WITH 200#.

REMARKS: USED 60/40 POZMIX 4% GEL BY UNITED CEMENTING & ACID CO., INC.

NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING OCT 05 1999

SIGNED

Stephen J. Pfeifer
(TECHNICIAN)

FORM CP-2/3