

2 070163

4-20

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-20,789-0001
SE, SEC. 14, T 27 S, R 10W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5047
Operator: Rupe Oil Co., Inc.
Name & Address: P. O. Box 2273
Wichita, KS 67201

feet from N/S section line
640 feet from W/E section line
Lease Name Dyche Well # 1
County Kingman 140.73
Well Total Depth 4330 feet
Conductor Pipe: Size feet
Surface Casing: Size 8-5/8 feet 272

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105
Address Box 186, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:00 Day: 20 Month: 4 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: Sand bottom to 3960' & 5 sx common - 35 sx at 1500' - 35 sx at 1000' -
330' to surface.

Plugging Proposal Received by John Sanders (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:50 Day: 20 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT Sanded bottom to 3960' & 5 sx common - pulled 1700' of 5-1/2" ran tubing in to 1500' & B? J. Titan pumped 35 sx - pulled tubing to 1000' & pumped 35 sx - pulled tubing to 330' & pumped 92 sx to surface - used 60/40 2% gel 2% cc - Titan #513080

RECEIVED STATE CORPORATION COMMISSION

MAY - 7 1989

Remarks: Docket #CD-18,244 & C-20,562

INVOICED

If additional description is necessary, use BACK of this

CONSERVATION DIVISION
Wichita, Kansas

DATE 5-8-89
INV. NO. 24641

Signed [Signature] (TECHNICIAN)