

1 051255

12-28

273

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,106-0000
C NW NE, SEC. 4, T 27 S, R 16 W/E
4620 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414

Lease Name Jewitt Well # 1

Operator: J. Mark Richardson

County Kiowa 148.14

Name & Address 155 North Market, Suite 840
Wichita, KS 67202

Well Total Depth 4558 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 381

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Greensburg Well Service License Number _____

Address 303 East Kansas, Greensburg, KS 67054

Company to plug at: Hour: 9 a.m. Day: 28 Month: 12 Year: 19 89

Plugging proposal received from Carl Schield

(company name) Greensburg Well Service (phone) 316-723-2204

were: 4 1/2" at 4555' PBD 4550' Perfs at 4493-96' Elevation 2099' GL

1st plug sand back to 4430' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a. Day: 28 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4430' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2878' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-22-90

WEL. NO. 27038

12-28

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lacey
(TECHNICIAN)