

1041376

TO: STATE CORPORATION COMMISSION

API NUMBER 15-097-20,717-0000
C SE/4 SE/4 NE/4 SEC. 24, T 27 S, R 16 W

CONSERVATION DIVISION - PLUGGING SECTION 2970 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BUTLER-THOMPSON WELL # 2-24

TECHNICIAN'S PLUGGING REPORT

12/10

COUNTY KIOWA

149.60

OPERATOR LICENSE # 5004

WELL TOTAL DEPTH 4603 FEET

OPERATOR: VINCENT OIL CORPORATION PRODUCTION CSG: SIZE 5 1/2" @ 4603' WITH 200 SX

NAME AND 125 N MARKET #1075 SURFACE CASING: SIZE 8 5/8" @ 372' WITH 325 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 BETH DRIVE, STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 3:30 PM DAY: 10 MONTH: 12 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 4574-82 & 4440-45

SANDED BACK TO 4400' AND PUT 5 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER. LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 1100' WITH 50 SX CEMENT. 2ND PLUG AT 400' WITH 50 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 10 MONTH: 12 YEAR: 1999

ACTUAL PLUGGING REPORT _____

SANDED BACK TO 4400' AND PUT 5 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER. LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 1100' WITH 50 SX CEMENT. 2ND PLUG AT 400' WITH 50 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

Conservation Division
Wichita, Kansas

DEC 22 1999

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2641' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF FORM.)

I (DID) OBSERVE THIS PLUGGING

INVOICED

SIGNED Stephen J. Barber
(TECHNICIAN) FORM CP-2/3

DATE 12/22/99

INV. NO. 061022