

1041344

TO: STATE CORPORATION COMMISSION

4-9

API NUMBER 15-097-20,725-0000
NE SE SE SEC. 24, T 27 S, R 16 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME CLARKSON WELL # 4-24

TECHNICIAN'S PLUGGING REPORT

COUNTY KIOWA

OPERATOR LICENSE # 31925

WELL TOTAL DEPTH 4641 150.84 FEET

OPERATOR: QUALITY WELL SERVICE

PRODUCTION CSG: SIZE 4 1/2" @ 4639' WITH 200 SX

NAME AND 249 BETH DRIVE

SURFACE CASING: SIZE 8 5/8" @ 362' WITH 300 SX

ADDRESS STERLING, KS 67579

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS SAME AS ABOVE

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 09 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 4552-60

1ST PLUG SAND BACK TO 4486' WITH 4 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER.

LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING.

2ND PLUG AT 1080' WITH 50 SX CEMENT. 3RD PLUG AT 400' WITH 50 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:30 AM DAY: 09 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SANDED BACK TO 4486' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THRU BAILER.

LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING.

2ND PLUG AT 1080' WITH 50 SX CEMENT.

3RD PLUG AT 400' WITH 50 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY UNITED CEMENTING. RECOVERED 2320' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED

DATE APR 16 1999

APR 13 1999

SIGNED

Steve Pfeifer / S.P.
(TECHNICIAN) FORM CP-2/3

INV. NO. 60851

CONSERVATION DIVISION
Wichita, Kansas