

1070092

TO: STATE CORPORATION COMMISSION

API NUMBER 15-097-20,549-0000
C W/2 SW SEC. 24, T 27 S, R 16 W

4-16

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4620 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME CLARKSON WELL # 1-24

TECHNICIAN'S PLUGGING REPORT COUNTY KIOWA 152.04

OPERATOR LICENSE # 31925 WELL TOTAL DEPTH 4678 FEET

OPERATOR: QUALITY WELL SERVICE PRODUCTION CSG: SIZE 4 1/2" @ 4677' WITH 200 SX

NAME AND 249 BETH DRIVE SURFACE CASING: SIZE 8 5/8" @ 361' WITH 300 SX

ADDRESS STERLING, KS 67579

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS SAME AS ABOVE

COMPANY TO PLUG AT: HOUR: 1:15 PM DAY: 16 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 4332-4337, CIBP @ 4450, PERFS @ 4564-68

1ST PLUG SAND BACK TO 4271' WITH 4SX CEMENT.

2ND PLUG SPOT 50 SX CEMENT AT 1060'. 3RD PLUG SPOT 50 SX CEMENT AT 390'. 7 SX GEL TOTAL

SPACERS. 4TH PLUG SPOT 10 SX CEMENT AT 0-40'.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 2:30 PM DAY: 16 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT'

1ST PLUG SAND TO 4271' WITH 4 SX CEMENT.

2ND PLUG SPOT 50 SX CEMENT AT 1060'.

3RD PLUG SPOT 50 SX CEMENT AT 390'. 7 SX GEL TOTAL SPACERS.

4TH PLUG SPOT 10 SX CEMENT AT 0-40'. GOOD CIRCULATION THROUGHOUT JOB.

REMARKS: USED 60/40 POZMIX 6% GEL BY UNITED. RECOVERED 2220' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED
I (DID) OBSERVE THIS PLUGGING STATE CORPORATION

SIGNED

(TECHNICIAN) FORM CP-2/3

DATE 4-30-99
INV. NO. 60906

RECEIVED
APR 26 1999
4-26-99
CONSERVATION DIVISION
Wichita, Kansas