

1041345

TO: STATE CORPORATION COMMISSION

4-19

API NUMBER 15-097-20,593-0000  
C NE SW SEC. 24, T 27 S, R 16 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME CLARKSON WELL # 2-24

TECHNICIAN'S PLUGGING REPORT

COUNTY KIOWA 151.97

OPERATOR LICENSE # 31925 WELL TOTAL DEPTH 4676 FEET

OPERATOR: QUALITY WELL SERVICE PRODUCTION CSG: SIZE 4 1/2" @ 4675' WITH 300 SX

NAME AND 249 BETH DRIVE SURFACE CASING: SIZE 8 5/8" @ 370' WITH 300 SX

ADDRESS STERLING, KS 67579

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS SAME AS ABOVE

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 19 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 4597-99, 4508-09, & 4503-07

1ST PLUG SANDED BACK TO 4450' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE.

LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING. 2ND PLUG AT 1080' WITH 50 SX CEMENT.

3RD PLUG AT 400' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 19 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SANDED BACK TO 4450' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE.

LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING.

2ND PLUG AT 1080' WITH 50 SX CEMENT.

3RD PLUG AT 400' WITH 50 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY UNITED CEMENTING & ACID CO. RECOVERED 2220' OF 4 1/2".  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING:

SIGNED

Signature of Stephen J. Pfeifer (TECHNICIAN) FORM OF-2/3

INVOICED

DATE 5-7-99

MAY 06 1999 5-06-99 CONSERVATION DIVISION Wichita, Kansas

WEL. NO. 60933