

1052310

TO: STATE CORPORATION COMMISSION

4-13

API NUMBER 15-097-20,705-0000
NE NE SE SEC. 24, T 27 S, R 16 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME CLARKSON WELL # 3-24

TECHNICIAN'S PLUGGING REPORT COUNTY KIOWA 118.92

OPERATOR LICENSE # 31925 WELL TOTAL DEPTH 4582 FEET

OPERATOR: QUALITY WELL SERVICE PRODUCTION CSG: SIZE 5 1/2" @ 4576' WITH 200 SX

NAME AND 249 BETH DRIVE SURFACE CASING: SIZE 8 5/8" @ 404' WITH 300 SX

ADDRESS STERLING, KS 67579

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS SAME AS ABOVE

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 13 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 4321-25, 4442-46

1ST PLUG SANDED TO 4270' AND 5 SX CEMENT.

SPOT PLUGS THROUGH CASING. 2ND PLUG AT 1060' WITH 2 SX GEL - 50 SX CEMENT - 4 SX GEL.

3RD PLUG AT 440' WITH 50 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:35 PM DAY: 13 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SAND TO 4270' AND 5 SX CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

SPOT PLUGS THROUGH CASING.

APR 22 1999

2ND PLUG AT 1060' WITH 2 SX GEL - 50 SX CEMENT - 4 SX GEL.

CONSERVATION DIVISION
Wichita, Kansas

3RD PLUG AT 440' WITH 50 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY UNITED. RECOVERED 2537' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard M. Lacy (TECHNICIAN) FORM CP-2/3

INVOICED

DATE APR 28 1999

INV. NO. 60890