

1041411

TO: STATE CORPORATION COMMISSION

API NUMBER 15-097-21,089-0000
NE NE NE SEC. 21, T 27 S, R 16 W

CONSERVATION DIVISION - PLUGGING SECTION 4950 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME CLARK B WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY KIOWA 162.50

OPERATOR LICENSE # 5414

WELL TOTAL DEPTH 5000 FEET

OPERATOR: J MARK RICHARDSON PRODUCTION CSG: SIZE 4 1/2" @ 4998' WITH 250 SX

NAME AND 2843 KEYWEST CT. SURFACE CASING: SIZE 8 5/8" @ 433' WITH 300 SX

ADDRESS WICHITA, KS 67204

ABANDONED OIL WELL GAS WELL INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR KLIMA WELL SERVICE INC. LICENSE NUMBER 7023

ADDRESS PO BOX 386 CLAFLIN, KS 67525-0386

COMPANY TO PLUG AT: HOUR: 9:45 AM DAY: 26 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM CARL SCHIELD STATE CORPORATION COMMISSION

(COMPANY NAME) KLIMA WELL SERVICE (PHONE) 316-587-3333 **RECEIVED**
AUG - 8 2000

WERE: CIBP @ 3790, 3690, 3700, 3669, 4800, & 4644. PERFS AT 3551-55, 3563-65 CONSERVATION DIVISION
Wichita, Kansas

SANDED BACK TO 3450' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER.

PUMP DOWN 8 5/8" WITH 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS, 8 5/8" WIPER

PLUG, & 150 SX CEMENT. MAXIMUM PRESSURE 400#. SHUT IN PRESSURE 150#.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 10:45 AM DAY: 26 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT _____

SANDED BACK TO 3450' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER.

PUMP DOWN 8 5/8" WITH 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS, 8 5/8" WIPER

PLUG, & 150 SX CEMENT. MAXIMUM PRESSURE 400#. SHUT IN PRESSURE 150#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2304' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

INVOICED
DATE 8/10/00 SIGNED _____
WV, NO. 1060329

Stephen J. Pfeifer
(TECHNICIAN) FORM CP-2/3

