

State of Kansas



FORM - CP-2
Rev. 8-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

November 10, 1963

15-155-00123-0000 RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1963

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

11-18-1963

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this

date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Harvey Rosen

Complete Address: 5405 East Central, Wichita, Kansas

Lease Name: Stucky Well No. 1

Location: SW SW SW Sec. 14 Twp. 26 Rge. 6 (E) (W) X

County Reno Total Depth 4200' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Push 5 1/2" plug to 3610'. Fill hole with sand to 3600' and
cement with 5 sacks. Fill hole with mud to 260'. Set
rock bridge from 260' to 250' and cement hole with 25 sacks.
Fill hole with mud to 30'. Set rock bridge from 30' to 20'
and cap hole with 10 sacks cement.

Very truly yours,

William J. Loman