



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-155-30092-0000

RECEIVED
STATE CORPORATION COMMISSION

DEC 15 1965

CONSERVATION DIVISION
WICHITA, KANSAS

Dec. 12, 1965.

12-15-1965

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Pancraft of H-30 has this

date requested permission to plug the following described well:

Mr. Pancraft guarantees payment of the plugging fee.

Operator's full Name: H-30

Complete Address: 200 N. Main Wichita, Kansas.

Lease Name: Graber Well No. #1

Location: C-NE-SE Sec. 13 Twp. 26 Rge. 7 (E)(W) W

County: Reno Total Depth 4130' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pancraft was instructed to plug the well as follows:

190' of 8 5/8" surface pipe circulated with cement. Heavy
drill mud to 180'. First plug & 1 sack hulls and 20 sacks cement.
Hole filled with mud to 40', second plug & 1 sack hulls and 10
sacks cement to base of cellar, 2 sacks cement in rat hole.

Very truly yours,

Hermon Justice
Conservation Division Agent