



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

May 17, 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-155-20755-0000

Dear Sir:

Mr. Harlan Yoesel of Brandt Drilling Co. has this

date requested permission to plug the following described well:

Operator's Full Name: Raymond Oil Company, Inc.

Complete Address: One Main Place # 900, Wichita, Kansas 67202

Lease Name: Koontz Well No. 1

Location: 100' E of C SW SE SW Sec. 3 Twp. 26 Rge. 4 ~~(E)~~ (W)

County: Reno Total Depth: 3365'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Yoesel was instructed to plug the well as follows:

8-5/8"-200'-circulated Hole filled with mud. Pump 50 sacks 50-50 pozmix
w/4% gel and 3% cal. Chlor. through drill pipe at 300'. Fill hole with
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10
sacks cement. Cement rathole with 5 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 22 1981

Very truly yours,

CONSERVATION DIVISION
Wichita, Kansas

[Signature]
Conservation Division Agent

5-22-1981