



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-155-02089-0060

July 6, 1964

RECEIVED
STATE CORPORATION COMMISSION

JUL 10 1964

CONSERVATION DIVISION
Wichita, Kansas

7-10-1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Rod Sweetman of S & S Drilling Company has this

date requested permission to plug the following described well:

Mr. Sweetman guarantees payment of the plugging fee.

Operator's full Name: V. E. Wiggins

Complete Address: Box 191, McPherson, Kansas

Lease Name: Holtje Well No. 1

Location: NE SE SE Sec. 16 Twp. 26 Rge. 4 (W) X

County Reno Total Depth 4081' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole


Mr. Sweetman was instructed to plug the well as follows:

Fill hole with mud to 160'. Push plug and 1/2 sack hulls
to 160' and cement hole with 20 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and 1/2 sack hulls
to 40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,


Conservation Division Agent