



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

15-55-00430-0000

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 September 11, 1964

SEP 23 1964

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

9-23-1964

Dear Sir:

Mr. Art Lamb of Lamb Casing Pulling Co. has this

date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: V. E. Wiggins

Complete Address: Box 191, Mc Pherson, Kansas

Lease Name: Seidi Well No. 1

Location: NE SE NE Sec. 21 Twp. 26 Rge. 4 ~~NE~~ (W) X

County Reno Total Depth 4075' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Wiggins was instructed to plug the well as follows:

Push 5 1/2" plug to 3215'. Fill hole with sand to 3205' and
cement hole with 5 sacks. Fill hole with mud to 185'.

Set rock bridge from 185' to 175' and cement hole with 20
sacks. Fill hole with mud to 40'. Set rock bridge from
40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent