


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ford County, Sec. 11 Twp. 27S Rge. (X) 22 (W)
Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner Graves Drilling Co., Inc.
Lease Name Konda Well No. 1
Office Address 412 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 7, 1966
Application for plugging filed October 7, 1966
Application for plugging approved October 7, 1966
Plugging commenced October 7, 1966
Plugging completed October 7, 1966
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well E. Eves, Box "F", Sublette, Kansas
Producing formation Depth to top Bottom Total Depth of Well 1480 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 700 feet. Followed by wooden plug and 1/4 sack hulls. Placed 15 sacks cement onto hulls. Mudded up with heavy mud to 350 feet followed by wooden plug and 15 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1966
11-8-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graves Drilling Co., Inc.
Address 412 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
412 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of October, 1966

My commission expires April 30, 1967
Betty Brandt
Betty Brandt Notary Public.

R O T A R Y D R I L L E R S ' L O G

OPERATOR: Graves Drilling Co., Inc. DRILLING COMMENCED: October 5, 1966
412 Union Center
Wichita, Kansas

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: October 7, 1966
412 Union Center
Wichita, Kansas

CASING RECORD: None set LOCATION: Konda No. 1
NW NW SW
Section 11-27S-22W
Ford County, Kansas

0 - 300	Sod, clay & shale
300 - 705	Shale
705 - 750	Sand
750 - 1084	Shale, sand & lime streaks
1084 - 1431	Red bed & shale
1431 - 1480	Anhydrite
1480	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1966
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By Paul Graves
President

STATE OF KANSAS)
) SS:
BUTLER COUNTY)

Subscribed and sworn to before me, a Notary Public, this 28th of October, 1966.

Betty Brandt
Betty Brandt Notary Public

My commission expires:
April 30, 1967