

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kiowa County, Sec. 35 Twp. 27 Rge. 20 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

C NE NW

Lease Owner J. Mark Richardson
Lease Name Brensing #1 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6/16/80 _____ 19____
Plugging completed 6/21/80 _____ 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production
_____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4879
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	595	none
				4 $\frac{1}{2}$ "	4877	2730'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 4800' and ran 4 sacks cement. Shot pipe at 4035', 3825', 3635', 3505', pulled 8 joints and well blew in. Pumped 22 bbls. salt water down 4 $\frac{1}{2}$ ", shot pipe at 3145', 3010', 2810', 2640', 2450', pulled 73 joints. Squeezed hole with 15 sacks gel, 8 sacks hulls, 10 sacks gel. Released plug and displaced with 125 sacks 50-50 pozmix, 4% gel and 3% cc.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1980

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of June, 19 80

My commission expires



Margaret Melcher
Notary Public.

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Breasing #1
 C-NE-NW Sec 35-27S-20W
 Kiowa County Kansas

Commenced: 12-11-76

Completed: 12-22-76

OPERATOR: J. MARK RICHARDSON

Depth		Formation	Remarks
From	to		
0	175	Sand	Ran 15 jts of 28# 8 5/8" csg set @ 595' Cemented w/ 200 sks common 3% CC-2% Gel + 200' sks Common 3% CC PD @ 9:00 p.m. 12-11-76
175	300	Redbed	
300	602	Shale	
602	1270	Shale-Shells	
1270	1307	Anhy	
1307	2325	Shale-Shells	
2325	2675	Shale-Lime	Ran 145 jts of 10 1/2# 4 1/2" csg set @ 4877' Cemented w/ 20 bbls Salt Flush - 125 sks 50/50 Posmix 18% Salt 1/2 of 1% CFR-2 PD @ 6:15 a.m. 12-22-76
2675	2885	Shale-Shells	
2885	3030	Lime	
3030	3350	Shale-Lime	
3350	3856	Lime-Shale	
3856	4330	Shale-Lime	
4330	4879	Lime	
4879 - TD			

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
 Drillers Well Log is true and correct to the best of my knowledge and belief and
 according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me this 29th day of December, 1976.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission Expires 2-8-78

