

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County, Sec. 26 Twp. 27S Rge. 20W (E) (W)

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines C SE NW  
Lease Owner Walters Drilling Co. & Northern Natural et al  
Lease Name Tucker Well No. 1  
Office Address 510 Orpheum Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-4-64 19  
Application for plugging filed 5-4-64 19  
Application for plugging approved 5-4-64 19  
Plugging commenced 5-4-64 19  
Plugging completed 5-4-64 19  
Reason for abandonment of well or producing formation commercial quantities of oil not found  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4933 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE  | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8 5/8 | 490    |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom plug @ 300' w/ Hulls & 25#sx. cement  
Top plug @ 40' w/ Hulls & 10 sx. cement

RECEIVED  
STATE CORPORATION COMMISSION

5-13-64  
MAY 13 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Walters Drilling Co.  
Address 510 Orpheum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Robert F. Walters (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert F. Walters  
510 Orpheum Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of May, 1964



Juanita M. Green  
Notary Public.

DRILLER'S LOG

COMPANY: WALTERS DRILLING CO. & NORTHERN NATURAL ET AL  
510 ORPHEUM BUILDING  
WICHITA, KANSAS

WELL NAME: TUCKER #1  
C SE NW SEC. 26-27S-20W  
KIOWA COUNTY, KANSAS

CONTRACTOR: WALTERS DRILLING CO.  
510 ORPHEUM BUILDING  
WICHITA, KANSAS

ROTARY DRILLING COMMENCED: APRIL 21, 1964

ROTARY DRILLING COMPLETED: MAY 4, 1964

ELEVATION: 2282 KB  
2279 DF  
2277 GL

CASING RECORD: 8 5/8" set @ 490' w/ 285 sacks cement

LOG

|             |                                       |
|-------------|---------------------------------------|
| 0 - 50      | Sand                                  |
| 50 - 502    | Shale and Sand                        |
| 502 - 565   | Sand                                  |
| 565 - 700   | Red Rock and Shale                    |
| 700 - 715   | Lime                                  |
| 715 - 725   | Red Rock and Shale                    |
| 725 - 1265  | Shale and Red Bed                     |
| 1265 - 1280 | Anhydrite                             |
| 1280 - 1350 | Shale and Shells                      |
| 1350 - 1755 | Shale                                 |
| 1755 - 2320 | Shale and Shells                      |
| 2320 - 2840 | Lime and Shale                        |
| 2840 - 3315 | Shale and Lime                        |
| 3315 - 3437 | Lime and Shale                        |
| 3437 - 3880 | Shale and Lime                        |
| 3880 - 4185 | Lime and Shale                        |
| 4185 - 4224 | Shale                                 |
| 4224 - 4288 | Lime                                  |
| 4288 - 4335 | Lime and Shale                        |
| 4335 - 4611 | Lime                                  |
| 4611 - 4668 | Lime and Shale                        |
| 4668 - 4758 | Lime                                  |
| 4758 - 4820 | Lime and Shale                        |
| 4820 - 4839 | Lime                                  |
| 4839 - 4846 | Core #1                               |
| 4846 - 4862 | Core #2                               |
| 4862 - 4876 | Core #3                               |
| 4839 - 4872 | Reamed (core hole)                    |
| 4872 - 4896 | Reamed (core hole)                    |
| 4876 - 4920 | Miss. Lime and Chert                  |
| 4920 - 4933 | Cherty Lime                           |
| <u>4933</u> | <u>Rotary Total Depth - D &amp; A</u> |

RECEIVED  
STATE CORPORATION COMMISSION

MAY 13 1964

CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, Robert F. Walters, hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

BY

  
ROBERT F. WALTERS, Partner


STATE OF KANSAS )  
                          ) SS.  
COUNTY OF SEDGWICK)

BE IT REMEMBERED that, on this 8th day of May, 1964, before me, the undersigned, a Notary Public duly commissioned in and for the State and County aforesaid, came Robert F. Walters, known to me to be the same person who executed the foregoing instrument as Partner and in behalf of the Walters Drilling Co. and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

My Commission Expires:

October 4, 1967



*Juanita M. Green*  
\_\_\_\_\_  
Juanita M. Green, Notary Public