

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

KIOWA County. Sec. 26 Twp. 27S Rge. (E) 20 (W)

Location as "NE/CNW/SW" or footage from lines C SW SE
Lease Owner J. MARK RICHARDSON
Lease Name NELSON Well No. 1
Office Address 200 O. W. GARVEY BUILDING, WICHITA, KANSAS 67202
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 2/14 19 76
Application for plugging filed 2/14 19 76
Application for plugging approved 2/14 19 76
Plugging commenced 2/14 19 76
Plugging completed 2/14 19 76
Reason for abandonment of well or producing formation DRY HOLE



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? VERBAL APPROVAL

Name of Conservation Agent who supervised plugging of this well G. R. BIBERSTEIN
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4895 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand, shale-shells, sand and shale		0	602	8 5/8	602	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug No. 1 @ 350' w/35 sx
Plug and bridge @ 40' with 15 sx
Hole D & A at 9 PM

RECORDED
INDEXED
5-3-76
Conservation Division
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GABBERT-JONES, INC.
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
GABBERT JONES INC. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) JACK GABBERT
830 Sutton Place, Wichita, Kansas (Address)



Subscribed and sworn to before me this 30 day of April, 19 76
Nov. 29, 1979
Marjorie Hall Notary Public.

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Nelson #1
 C-SW-SE Sec 26-27S-20W
 Kiowa County Kansas

Commenced: 2-4-76

Completed: 2-14-76

OPERATOR: J. MARK RICEARDSON

From	Depth to	Formation	Remarks
0	120	Sand	Ran 15 jts of used 28# 8 5/8"
120	475	Shale-Shells	csq sct @ 602' Cemented
475	545	Sand-Shale	w/220 sks Common 3% CC
545	608	Shale-Shells	2% Gel - 200 sks Common
608	720	Hard Sand	3% CC PD @ 5:30 a.m. 2-5-76
720	1263	Shale-Redbed-Shells	
1263	1280	Anhy	
1280	1795	Shale-Shells	
1795	2470	Shale-Lime	
2470	2685	Shale	
2685	3070	Lime	
3070	3240	Lime-Shale	
3240	3380	Lime	
3380	3540	Lime-Shale	
3540	3950	Lime	
3950	4165	Lime-Shale	
4165	4895	Lime	
	4895 - TD		

RECORDED
 MAR 03 1976
 COUNTY OF SEDGWICK
 WICHITA, KANSAS

DRY & ABANDONED

I, James S. Sutton II, certify this is a correct copy for the Drillers' Log for the well drilled C-SW-SE Sec 26-27S-20W, Kiowa County, Kansas to the best of my knowledge and belief.

James S. Sutton II
 JAMES S. SUTTON II

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 1st day of March, 1976, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission Expires: February 6, 1979.

