

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-097-00220-0001

#1 API NUMBER N/A

LEASE NAME Nelson D #1

WELL NUMBER \_\_\_\_\_

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 27 TWP. 27S RGE. 20 (~~xx~~ or (W))

COUNTY Kiowa

Date Well Completed 4-28-64

Plugging Commenced 4-20-83

Plugging Completed 6-16-83

LEASE OPERATOR J. Mark Richardson

ADDRESS 640 Century Plaza Bldg., Wichita, Ks. 67202

PHONE# (316) 262-3192 OPERATORS LICENSE NO. 5414

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes ~~no~~, is well log attached? yes

~~SWD~~ Formation Mississippi Warsaw Depth to Top 4876 Bottom 4886 T.D. 4980  
Dolomite

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From 0	To 504	Size	Put in 504 in	Pulled out
				8 5/8		
				4 1/2	4079	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet, each set. Pumped 3 sacks hulls, 10 sacks gell, 70 sacks common cement, 4 sacks hulls, 10 sacks cement into the 4 1/2" casing and pressured up okay; then pumped into 8 5/8" surface pipe. At 400#, cement came up to surface on outside of 8 5/8. 6-16-86 Pumped 100 sx. common into 4 1/2 @ 700#. Went into annulus, pumped 40 sacks into annulus. Had leak in the same place. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address P.O. Box 31, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.

J. Mark Richardson (Employee of operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J. Mark Richardson

(Address) 640 Century Plaza Bldg. Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 24th day of June, 19 86

JUDY L. McMINN  
NOTARY PUBLIC  
STATE OF KANSAS  
My Commission Expires 10-30-88

Judy L. McMinn  
STATE CORPORATION COMMISSION

JUN 24 1986

CONSERVATION DIVISION  
Wichita, Kansas

Form CP-4  
Revised 08-84

Requested and obtained permission from the Corporation Commission to cut off the Braden Head and cement surface with 1" pipe.

NOTE: This well was originally the Walters Drilling Company Nelson "D" #1.

ALL INFORMATION CONTAINED  
HEREIN IS UNCLASSIFIED  
DATE 10/15/2001 BY 60322  
UCBA/STP

WALTERS DRILLING COMPANY