


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pratt County. Sec. 17 Twp. 27 Rge. 12 (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NW SW
Lease Owner Specter Pipe & Supply Company, Inc
Lease Name Hoema Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 7-4-57 19__
Application for plugging filed June 2, 1970 19__
Application for plugging approved June 20, 1970 19__
Plugging commenced June, 17, 1970 19__
Plugging completed June, 26, 1970 19__
Reason for abandonment of well or producing formation failure to produce profitably
If a producing well is abandoned, date of last production _____ 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G.R. Biberstein
Producing formation Arbuckle Depth to top 4438 Bottom 4455 Total Depth of Well 4465 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE #	PUT IN	PULLED OUT
				8 5/8" OD	315 ft.	none
				5 1/2" OD	4455 ft.	3112 feet

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged, back to 3700- feet, sand to 3670- feet.
Dumped 5- sacks Cement, Set a ten foot rock Bridge, from 300- feet to 290- feet.
25- sacks Cement, Mudded hole up to 40- feet.
et a ten foot Rock Bridge, ten sacks on top.

RECEIVED
STATE CORPORATION COMMISSION
JUL 6 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Lynch Casing Pulling Company, No. 457
Address R.Rt. 4 Great Bend, Kansas, 67530

STATE OF Kansas COUNTY OF Russell, ss.
Specter Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 169, Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of June, 1970

My commission expires May 21, 1971
Thelma M. Lindahl Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- MONSANTO CHEMICAL CO.
Farm- Hoeme No. 1

SEC. 17 T. 27 R. 12W
NE NW SW

Total Depth. 4465'
Comm. 6-15-57 Comp. 7-4-57
Shot or Treated.
Contractor. Lauck Drlg. Co., Inc.
Issued. 9-28-57

County Pratt
KANSAS



Elevation. 1852' DF

Production. 146 BOPD

CASINO:

8 5/8" 315' w/200 sx cem.
5 1/2" 4455' w/200 sx cem.

Figures indicate Bottom of Formations.

sand-clay	115
red bed	315
red bed-shale	1065
shale-shells	1700
lime-shale	2310
lime brkn	2400
shale-lime	2665
shale-shells	2845
shale-lime	3063
brkn lime	3075
shale-lime	3363
lime	4125
lime-shale	4142
cherty lime	4180
lime	4225
chert	4235
lime	4274
lime-chert	4285
chert	4315
lime	4336
Simpson-Diamond core	4371
sand	4380
shale-sand	4397
shale-lime	4444
lime	4465 RTD

TOPS:	SAMPLE	HALL.
Heebner	3502	3500
Toronto	3519	3516
Douglas shale	3542	3541
Brown lime	3679	3678
Lansing-Kansas City	3697	3696
B/Kansas City	4043	4042
Mississippian	4146	4141
Viola	4285	4284
Simpson	4313	4312
Simpson sand	4345	4345
Simpson shale	4391	4392
Arbuckle	4438=	4438

Cored 4336-71 Rec. 35'.

DST 4337-71 Open 45 mins., gas to surface in 7 min., oil to the surface in 41 mins., gas gauged 200 MCF in 15 mins., TSTM in 25 mins., Reversed circulated fluid, rec. 135' wtr below reverse circulating sub, L.F. 218#, FF 743#, ISIP 1279# in 20 mins., HHP 1279# in 1 hr.

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1970
CONSERVATION DIVISION
Wichita, Kansas