

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER \_\_\_\_\_

LEASE NAME Hoeme B #1

WELL NUMBER \_\_\_\_\_

SPOT LOCATION C. S/2' SE NW

SEC. 17 TWP. 27 RGE. 12 (E) or (W)

COUNTY Pratt

Date Well Completed \_\_\_\_\_

Plugging Commenced 10/16/84

Plugging Completed 10/19/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR D.R. Lauck Oil Co., Inc.

ADDRESS 221 S. Broadway, Suite 400, Wichita, Ks. 67202

PHONE # (316) 263-8267 OPERATORS LICENSE NO. 5427

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 2740'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	295'	none
				4 1/2"	2739'	2011'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged bottom with sand to 2630' & 4 sacks cement. Shot pipe at 2316', 2116', & 2011'. Pulled 63 joints. Plugged well with 3 hulls, 10 gel, 70 cement, 10 gel, 1 hull, 8 5/8 plug, & 120 sacks 60/40 poz 2% gel 3% c.e.

Plugging complete.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address Box 347, Chase, Ks. 67524

RECEIVED  
STATE CORPORATION COMMISS

STATE OF Kansas COUNTY OF Rice, ss. 10-31-84 OCT 31 1984

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CONSERVATION DIVISION  
Wichita, Kansas

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 29 day of October, 19 84



Irene Hoover  
Notary Public

My Commission expires: \_\_\_\_\_

D. R. Lauck Oil Company, Inc. - Hoeme "B" #1  
C S/2 SE NW Sec. 17-27S-12W  
Pratt County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.  
221 S. Broadway, Suite 400  
Wichita, Kansas 67202

Commenced: March 5, 1978  
Completed: March 9, 1978

Drillers Log

Sand	100
Red Bed	970
Shale & Shells	2165
Shale	2335
Shale & Lime	2582
Shale & Shells	2680
Core, Shale & Sand	2702
Shale & Shells	2740 RTD

Casing: 295' 8-5/8" cemented with 275 sacks Common Cement,  
2% Gel, 3% Calcium Chloride.  
2735' 4-1/2" cemented with 75 sacks Salt Saturated  
Pozmix Cement.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 07 1984  
CONSERVATION DIVISION  
Wichita, Kansas