

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-22,120-0000

LEASE NAME Hoeme

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4470 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 17 TWP. 27S RGE. 12 (X) or (W)

COUNTY Pratt

LEASE OPERATOR Rheem Resources, Inc.

ADDRESS 100 S. Main, Suite 505; Wichita, KS 67202

PHONE# (316) 262-5099 OPERATORS LICENSE NO. 31283

Date Well Completed Sept, '94

Character of Well Oil

Plugging Commenced 11-4-97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-13-97

The plugging proposal was approved on 10-17-97 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Mississippian Depth to Top 4141' Bottom 4320' T.D. 4400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippian	Oil & Water	4146'	4190'	10 3/4"	366'	None
				5 1/2"	4398'	2153'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, - from ___ feet to ___ feet each set.
See attached sheet for details

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 18 1997

Name of Plugging Contractor Pratt Well Service License No. 5893

Address Box 847; Pratt, KS 67124

CONSERVATION DIVISION
WICHITA, KS


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rheem Resources, Inc.

STATE OF Kansas COUNTY OF Pratt, ss.

Ronald S. Schraeder, Petr. Engr. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Ronald S. Schraeder

(Address) 212 N. Market, Suite 405



Wichita, KS 67202

Donna Clasen
Notary Public

My Commission Expires: 3/25/2001

PLUGGING PROCEDURE

#1 HOEME
150'S, C E/2 NE NE
Sec 17-T27S-R12W
Pratt County, Kansas

11-4-97. Ran Allied Cementing Co.'s wireline to bottom. Hit "fish" at 2960'. Pumped 20 barrels of water down well. Well taking water at a rate of 5½ barrels per minute at a pressure of 400#. Mixed and displaced 50 sacks of 60/40 pozmix cement and wiper plug down to a depth of 2900'. As cement hit lost tubing and bailer area of wellbore, pressure climbed to 400# at end of pumping. Released pressure back to pump truck and wiper held steady. Procedure was witnessed by Steve Pfeifer and Richard Lacey of the Kansas Corporation Commission.

11-7-97. Rigged up Pratt Well Service double drum unit. Dug out cellar with shovels to uncover the bradenhead. Pulled up on 5½" casing and removed slips from bradenhead. Rigged up Wedge Dia-Log. Ran free-point tool down 5½" casing. Found free-point at 2155'. Worked casing up and down between pulling 50,000# and 90,000# but could not free up the casing any deeper than 2155'. Pulled free-point tool and ran cut-off tool. Shot off casing at 2153'. Pulled casing and tallied same on ground. Overall tally (including threads) was 2,152.68'.

11-13-97. Allied Cementing Co. mixed and pumped 15 barrels of water containing 300# cotton seed hulls, then 25 barrels of water containing 10 sacks of gel, the 14 barrels of water containing 50 sacks of 60/40 pozmix cement (6% gel), then 25 barrels of water containing 10 sacks of gel and 100# of cotton seed hulls, all of which was displaced with 42 barrels of water containing 150 sacks of 60/40 pozmix cement (6% gel) down well. Average injection pressure was 200#. Instant shut down of 75#. Shut well in at 3:30 P.M. Procedure was witnessed by Steve Pfeifer of the Kansas Corporation Commission.

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 18 1997

CONSERVATION DIVISION
WICHITA, KS