


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

PRATT County, Sec. 17 Twp. 27s Rge. 12W ## (W)  
Location as "NE/CNW/SW" or footage from lines SW NW NW  
Lease Owner PETROLEUM, INC.  
Lease Name HOEME "C" Well No. 4  
Office Address ROUTE 2, GREAT BEND, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed NOVEMBER 7 19 59  
Application for plugging filed NOVEMBER 7 19 59  
Application for plugging approved NOVEMBER 7 19 59  
Plugging commenced NOVEMBER 7 19 59  
Plugging completed NOVEMBER 7 19 59  
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES

If a producing well is abandoned, date of last production NONE 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. LACKAMP, STAFFORD, KANSAS  
Producing formation -0- Depth to top --- Bottom --- Total Depth of Well 4437 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	261'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

MUD UP WITH HEAVY MUD TO 260' FOLLOWED BY A WOODEN PLUG AND 1/4 SACK OF HULLS.  
PLACED 18 SACKS OF CEMENT THROUGH DRILL PIPE ON TOP OF PLUG. MUD UP TO 40' FOLLOWED  
BY A WOODEN PLUG. FILLED HOLE TO BASE OF WELL CELLAR WITH 10 SACKS OF CEMENT.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 24 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor GARVEY DRILLING COMPANY  
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.  
DON SEARLE (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle  
ROUTE 2, GREAT BEND, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 20TH day of NOVEMBER, 19 59

My commission expires APRIL 14, 1963  
Arthur J. Wiles  
Notary Public.



# WELL LOG

COMPANY PETROLEUM, INCORPORATED

SEC. 17 T. 27S R. 12W

FARM HOEME "C" NO. 4


LOC. SW, NW, NW *R*

TOTAL DEPTH 4437'

COUNTY PRATT CO., KANSAS

COMM. October 23, 1959 COMP. November 7, 1959

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 261' W/225 sax.

ELEVATION 1870' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

90	Sand & gravel
720	Red bed
1200	Shale
1500	Shale & lime
1830	Lime & shale
2140	Lime
2610	Lime & shale
3110	Shale & lime
3405	Lime & shale
3540	Lime, shale & sand
3698	Shale & lime
4117	Lime
4169	Shale & lime
4222	Lime & chert
4232	Chert
4256	Lime & shale
4291	Lime & chert
4333	Lime & shale
4375	Chert
4390	Chert & sand
4420	Sand
4437	Lime & shale
4437	T. D.

**RECEIVED**  
STATE CORPORATION COMMISSION  
NOV 24 1959  
CONSERVATION DIVISION  
Wichita, Kansas

State of KANSAS  
County of BARTON } ss:

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #4 HOEME "C" well.

*Verne A. Morris*

Subscribed and sworn to before me this 14th day of November 1959

My Commission Expires: April 14, 1963

*Arthur J. Wales*  
NOTARY PUBLIC