


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

10

WELL PLUGGING RECORD



PRATT County. Sec. 17 Twp. 27 Rge. 12W (E) (W)
Location as "NE/CNW%SW%" or footage from lines SW SE NW
Lease Owner SANTA FE PIPE & SUPPLY
Lease Name HOEME "C" # 3 Well No. 3
Office Address P. O. BOX 562 - GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed JULY 3 19 59
Application for plugging filed JUNE 1 19 61
Application for plugging approved JUNE 12 19 61
Plugging commenced JUNE 13 19 61
Plugging completed JUNE 21 19 61
Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRED HAMPEL
Producing formation Depth to top Bottom Total Depth of Well 4449' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	279'	NONE
				5 1/2	4449'	3899'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4449'	-	4110'	FILLED WITH SAND
4110'	-	4080'	5 SACKS CEMENT
4080'	-	270'	MUD
270'	-	260'	ROCK BRIDGE
260'	-	200'	20 SACKS CEMENT
200'	-	35'	ROCK BRIDGE
35'	-	BASE	10 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION

10-23-61

OCT 23 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GLENN & SMITH PIPE PULLING COMPANY
Address P. O. BOX 114 - ELLINWOOD, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 562, Great Bend, ks
(Address)

SUBSCRIBED AND SWORN to before me this 18 day of OCTOBER, 1961

My commission expires May 19, 1962
[Signature] Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock;

Wichita, Kansas


COPY

Company- PETROLEUM, INC.
 Farm- Hoeme "C" No. 3

SEC. 17 T. 27 R. 12W
 SW SE NW

Total Depth. 4449'
 Comm. 6-16-59 Comp. 7-3-59
 Shot or Treated.
 Contractor. Garvey Drlg.
 Issued. 10-17-59

County Pratt
 KANSAS



CASING:

8 5/8" 279' cem w/225 sx.
 5 1/2" 4449' cem w/100 sx.

Elevation. 1851' DF

Production. 25 BOPD

Figures Indicate Bottom of Formations.

sand & gravel	106.
red bed	690
shale	1250
shale & lime	1745
lime & shale	1780
lime	1900
lime & shale streaks	2100
lime	2405
shale & lime	3270
lime & shale	3350
shale & lime	3522
lime & shale	3670
lime	4165
lime, shale & chert	4225
chert	4230
chert & lime	4330
shale & sand	4341
sand	4390
lime & shale	4430
lime	4449
Total Depth	

TOPS: SCOUT

Heebner	3498
Douglas	3534
Lansing	3691
Base Kansas City	4040
Mississippi	4133
Viola	4272
Simpson Shale	4303
Simpson Sand	4336
Arbuckle	4424

RECEIVED
 STATE CORPORATION
 OCT 23 1959
 CONSERVATION DIVISION
 Wichita, Kansas