

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-151-101610000 4-26-52
API NUMBER

LEASE NAME IC HU

WELL NUMBER 4-2

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

990 Ft. from S(N) Line of Section (circle one)

2310 Ft. from E(W) Line of Section (circle one)

LEASE OPERATOR Tuka Carmi Development

ADDRESS P.O. Box

CITY, STATE, ZIP Pratt, Kansas 67124

PHONE# 36 1-72-2531 OPERATORS LICENSE NO. 31739

Character of Well S.W.D. Docket No E6895
(Oil, Gas, D&A, ~~S.W.D.~~ Input, Water Supply Well)

SPOT LOCATION SW. NW. NE.

SEC. 6 TWP. 27 S. RGE 12 (E) or (W)

COUNTY Pratt

Date Well Completed April 1952

Date Plugging Commenced July 6, 1998

Date Plugging Completed July 13, 1998

The plugging proposal was approved on July 2, 1998 (date)

by Steve Pfeiffer (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation(s) Simpson Depth to Top 4233' Bottom 4258' T.D. 4270'

Show depth and thickness of all water, oil and gas formations.

PBTD 4266'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
	Surface Pipe	0'	860'	8 5/8"	860' ✓	0
	Casing	0'	4270'	5 1/2"	4270' ✓	1718'

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

(7-6) Tagged Bottom at 3639.85 Pumped 23 bbl. of Water - broke Circulation, pumped 25 SK cement. (7-10) - Tagged plug at 3438' - Free point 1740' Set off 5 1/2" Casing at 1718' (7-13) pumped 50 SK cement w/ 4% Calcium, at 888.8 ft. pulled 15 ft. to 405' waited 1 1/2 hrs. broke Circ. pumped 50 SK cement. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service Inc.

License No. 5056

Address P.O. Box 847 Pratt, KS 67124-0847

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Richard A. Farris

STATE OF Kansas COUNTY OF Pratt, ss.

Stephen E. Hart - Office Manager (Employee of Operator or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stephen E. Hart

(Address) c/o Pratt Well Service Inc.

SUBSCRIBED AND SWORN TO before me this 17th day of July, 1998

Kenneth W. Furgason
Notary Public

My Commission Expires: 06/19/00



Form CP-4
Revised 12-9.

Plugging Continued

(7-13 Cont.) pulled up to 62'; pumped 20 EX cement
to top. of surface pipe.