

1050618

15-081-10100-0001

Comp. 9-22-60

Reopened 12-8-64

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NE NE, SEC. 8, T 28 S, R 34 W/E

4620 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Fletcher "F" Well # 1

Operator: Cities Service Oil & Gas Corp.

County Haskell 186.00

Name & Address 3545 NW 58th Street

Well Total Depth 5723 feet

Oklahoma City, OK 73112

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 780

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Daco, Inc. License Number 6416

Address Drawer 3010, Borger, TX 79007

Company to plug at: Hour: 12:00 pm Day: 28 Month: August Year: 1985

Plugging proposal received from Charles Glasscock

(company name) Cities Service (phone) 405-949-4400

were: 5 1/2" at 5452' PBD 5383' Perfs at 5237-42', 5349-56' Pump through 5 1/2" with mud between plugs

1st plug RTBP at 5018 with 2 sx cement

2nd plug on stub with 50 sx cement

3rd plug at 1820' with 50 sx cement

4th plug at 820' with 50 sx cement

solid bridge

5th plug hulls - plug at 40' Plugging Proposal Received by Richard W. Lacey
cement to surface with 10 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 1:00 pm Day: 28 Month: August Year: 1985

ACTUAL PLUGGING REPORT Charles Glasscock called 8-26-85 and changed the order.

1st plug RTBP at 5018' with 2 sx cement, 2nd plug at 1328' with 50 sx cement

3rd plug at 820' with 50 sx cement, 4th plug & 5th plugs = solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement. as per Don C. Ubel

Remarks: Used Common cement by Daco. Recovered 1328' 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

(Do not) observe this plugging.

INVOICED

DATE 9/6/85

STATE CORPORATION COMMISSION

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 9881

SEP 3 1985

8-28