

5-14 15-081-10080-0001 48  
API NUMBER 15- Drill Completion Date 12/17/59 R

To: 1 090074  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW SE, SEC. 28, T 28 S, R 34 W  
1980 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5293  
Operator: Helmerich & Payne, Inc.  
Name & Address: Box 558  
Garden City, KS 67846

Lease Name Eubank Well # 4  
County Haskell 182.65  
Well Total Depth 5620 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 790

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Helmerich & Payne, Inc. License Number 5293

Address Box 558, Garden City, KS 67846

Company to plug at: Hour: 10:30 a.m. Day: 14 Month: 5 Year: 19 90

Plugging proposal received from Don Lamb

(company name) Helmerich & Payne, Inc. (phone) 316-276-3693

were: 2 7/8" tubing at 5608' 2 7/8" tubing at 4056' Dual completed well  
Squeezed at 1347' with 77 sx cement.

1st plug pump 50 lbs. hulls and 125 sx cement down 2 7/8" at 5608',

2nd plug pump 200 sx cement down backside. If it will not take, perforate 2 7/8" at 820'

and pump 200 sx cement down 2 7/8" and circulate to surface.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1 p.m. Day: 14 Month: 5 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 200 sx cement down 2 7/8" tubing set at 5608',

2nd plug pumped 50 lbs. hulls and 200 sx cement down 2 7/8" tubing set at 4056'.

3rd plug pumped 125 sx cement down 8 5/8" casing (mixed 100 lbs. hulls with last half of

cement). 1st 2nd 3rd

Maximum pressure 1000 psi 500 psi 600 psi.

Shut in pressure 550 psi 50 psi 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED  
I intend to observe this plugging.

DATE 5-22-90 5-16-90

Signed Michael R Wilson (TECHNICIAN)

INV. NO. 28190 CONSERVATION DIVISION Kansas  
5-14