

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-10065-00-01
Spot: CSENE Sec/Twnshp/Rge: 28-28S-34W
1980 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: EUBANK Well Number: 7
County: HASKELL Total Vertical Depth: 5560 feet

Operator License No.: 5293
Op Name: HELMERICH & PAYNE, INC.
Address: 1579 E. 21ST ST.
TULSA, OK 74017

Conductor Pipe: Size _____ feet: 8 1/80.70
Surface Casing: Size 8.625 feet: 859 WITH 400 SX CMT
Production: Size 4.5 feet: 5560 WITH 170 SX CMT
Liner: Size 2.875 feet: 5516 WITH 460 SX CMT

Well Type: EOR UIC Docket No: E17988.1 Date/Time to Plug: 07/31/2002 1:00 PM
Plug Co. License No.: 5287 Plug Co. Name: HALLIBURTON SERVICES
Proposal Rcvd. from: MITCH MCNEIL Company: HELMERICH & PAYNE Phone: (918) 748-0519

Proposed Plugging Method: SET CIBP @ 5420' WITH 2 SX CMT. MUD SPACER TO 900'. PERFORATE AT 900' & CIRCULATE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/02/2002 2:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:
PBDT 5528'. PERFS AT 5494-5514'. SET CIBP @ 5418' WITH 2 SX CMT. HOLE FULL OF 2% KCL FROM PREVIOUS WORK. PERFORATE AT 900', ESTABLISH CIRCULATION UP 4 1/2" X 8 5/8" ANNULUS. PUMP 145 SX CMT. FILL 2 7/8" & 4 1/2" X 8 5/8" ANNULUS FROM 900' TO SURFACE.

RECEIVED
AUG 07 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Jim Holland PIRETT
(TECHNICIAN)

INVOICED AUG 05 2002
DATE 8-7-02
INV. NO. 200.306.0178

Form 07-33