

RECEIVED
KANSAS CORPORATION COMMISSION

10-12

2-

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

OCT 15 1993

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-173-20,629-0000
SW SW SE, SECTION 32 TOWNSHIP 26 RANGE 1W

OPERATOR LICENSE # 4419 330 FEET FROM S SECTION LINE
2310 FEET FROM E SECTION LINE

OPERATOR BEAR PETROLEUM INC
NAME & BOX 438
ADDRESS HAYSVILLE, KS 67060

LEASE NAME: RINK #1
COUNTY: SEDGWICK
WELL TOTAL DEPTH: 3413' 110-92

PIPE: _____

SURFACE CASING: 10-3/4" @ 212'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: 4-1/2" @ 3405' - PERFS 2815-18'

PLUGGING CONTRACTOR: GRESSEL OILFIELD SERVICES
ADDRESS: _____ LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: _____
COMPANY NAME: _____ PHONE: _____

WERE: _____

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART () NONE (_____)

COMPLETED: HOUR: _____ DAY: 12 MONTH: 10 YEAR: 1993

ACTUAL PLUGGING REPORT:
SANDED BACK TO 3350' & C/W/4 SX CMT THRU DUMP BAILER
- PUSHED WOOD & RUBBER PLUG TO 2850' & SANDED BACK TO
2750' - C/W/4 SX CMT THRU DUMP BAILER - SHOT 4-1/2" OFF
@ 2418' & PULLED TO 280' - CIRC CMT TO SURF - PULLED
REST OF 4-1/2" CSG - TOPPED OFF.

REMARKS: UNITED #4529 60/40 2%

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE OCT 28 1993

INV. NO. 39056

Dave Wertz
DAVE WERTZ (AGENT)

FORM CP-2/3
REV. 3/90

DW