

6-26

2-060056 257 R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

15-173-01472-0000

API NUMBER: 9/2/45 D-01,320

C NW NW SW, SECTION 36 TOWNSHIP 26 RANGE 1W

OPERATOR LICENSE # 9663 2310 FEET FROM S SECTION LINE
4950 FEET FROM E SECTION LINE

OPERATOR Pioneer Exploration Co.
NAME & P. O. Box 691007
ADDRESS Houston, TX 77269

STATE CORPORATION COMMISSION

JUL 2 1991

LEASE NAME: Petrie #3
COUNTY: Sedgwick CONSERVATION DIVISION
Wichita, Kansas

WELL TOTAL DEPTH: 3452' 112.19

CONDUCTOR PIPE: " @ ' 1
SURFACE CASING: 10-3/4" @ 170'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SLD X D&A _____
OTHER WELL AS HEREINAFTER INDICATED: 7" @ 3398' 5 1/2" Liner 3378-3411' open hole
3411-52' - perf 3018-22' (?)

PLUGGING CONTRACTOR: Long Drilling Company
ADDRESS: P. O. Box 131, Hamilton, KS 66853 LICENSE: 6112

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 10 MONTH: 6 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Zafar Vllah
COMPANY NAME: Pioneer Exploration Company PHONE: 713-893-9400

WERE: S/B 50' on top perfs to 2970' - c/w 10 sx - rip 7" @
+ - 1500' - set cmt plug 250' to surface.

PLUGGING PROPOSAL RECEIVED BY: M. L. Korphage
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART (_____) NONE (_____)

COMPLETED: HOUR: _____ DAY: 26 MONTH: 6 YEAR: 1991

ACTUAL PLUGGING REPORT:
Sanded back to 2820' - stuck jar - tools 35' long while knocking out bridge @
2970' - ran 1" to 2870' & had good circ of wtr but no sand - lost 20 jts of 1" in hole
- ran cable knife on 2-3/8" tubing to 1750' - hung up - worked loose - left 10' tool & 2
jts in hole @ 1750' - ran cable knife in on sand line to 1650' & cut cable - ran
impression block to 1690' - had perfect circle of tubing collar on it - spotted 25 sx
cmt thru dump bailer @ 1690' - tagged cmt @ 1608' - ripped 7" @ 380' and ran tools
back in hole - hit solid bridge (shale) @ 240' - bailed down to 240' - dumped 5 yds
slurry in well bore - cmt did not circ - down 40' - used 18 sx to top off.

REMARKS: Allen #042180

I DID OBSERVE THIS PLUGGING.

INVOICED

Dave Wertz
Dave Wertz (AGENT)

DATE 7-18-91

INV. NO. 32293

FORM CP-2/3
REV. 3/90