

02- 60236

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-173-20664-00-00 Spot: SESESE
Sec: 12 Twnshp & Dir: 26 S Rng & Dir: 1 W
Feet: 380 frm N/S: S Feet: 350 frm E/W: E
Lease/Unit Name: MCKOWN Well Number: 3
County: SEDGWICK Total Vertical Depth: 4730 feet

Operator License No.: 8599
Operator Name: Catron Oil Division
Address: 6545 Bella Road
Wichita, KS 67204

6/8

Conductor Pipe: Size feet:
Surface Casing: Size feet: 200
Production: Size 5.5 feet: 3599 153.73

Well Type: SWD UIC Docket No: D23784.0 Date/Time to Plug: 06/08/2000 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: Quality Well Service, Inc.
Proposal Received from: Jim Catron Company Name: Catron Oil

OpRepPhoneNo:

Were: See actual report.

Plugging Proposal Received By: David Wertz Doug Louis WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/08/2000 7:38 PM

Actual Plugging Report:

Run tub to 3,100' spotted 50sxs tub parted while coming out of hole @ 2,100'. Loaded hole, spotted 35sxs @ 2,100'. Perfed 5 1/2" @ 250' run tub to 250', cmnt circ in 5 1/2". Run 1" to 146' on backside pumped 35sx(circ). Run 1" into 5 1/2" pumped 15sxs(circ).

RECEIVED
KCC DISTRICT #2
JUN 09 2000
WICHITA, KS

Remarks: United #1084 60/40 poz 4%gel

Anhydrite Plug: No BottomPlug: No DakotaPlug: No
Plugged through:

I (did) did not) observe this plugging.

INVOICED

Signed

David Wertz
(TECHNICIAN)

DATE 6/12/00

INV. NO. 61861