

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

4-21

^R

API NUMBER: 15-173-20701-000

C SW SW, SECTION 12 TOWNSHIP 26 RANGE 1W

OPERATOR LICENSE # 30841

660 FEET FROM S SECTION LINE

4620 FEET FROM E SECTION LINE

OPERATOR Consolidated Oil & Gas
NAME & 410 17th St. #2300
ADDRESS Denver, CO 80202

RECEIVED

KANSAS CORPORATION COMMISSION

MAY 2 3 1993

CONSERVATION DIVISION
WICHITA, KS

LEASE NAME: Wright 12-4 SWD

COUNTY: Sedgwick

WELL TOTAL DEPTH: 4082 132.64

PIPE: 5-1/2" @ 3578/150sx

SURFACE CASING: 10-3/4" @ 256' /200sx

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: O.H. 3578-4082

PLUGGING CONTRACTOR: Allied Cementing

ADDRESS: 24 Lincoln, Russel KS 67665

LICENSE: _____

COMPANY TO PLUG AT: HOUR: 4:00pm DAY: 20 MONTH: 4 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: J. A. Waechter

COMPANY NAME: Consolidated Oil and Gas PHONE: 316-893-1225

WERE: Sand 50' inside pipe and 50sx cmt- Perf at 1100 &
300 then run tubing & spot 35sx at 1100 and circ from
300 to surface.

PLUGGING PROPOSAL RECEIVED BY: J. L. Sanders

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL PART NONE

COMPLETED: HOUR: 11:00am DAY: 21 MONTH: 4 YEAR: 1993

ACTUAL PLUGGING REPORT:

Sanded w/ 8sx- Sand 50' inside 5-1/2" then ran tubing
and pumped 50sx of cmt on bottom(TOC 3480) Perf at 1100
& 300'. Ran tubing to 1129' & pumped 35sx of cmt to
1060'. Pulled tubing to 338' & circ w/ 200sx of cmt.
topped off well 4/22/93.


REMARKS: Alleid Cmt #5644 60/40 on 1100,300 plug-Common on bottom

I DID NOT OBSERVE THIS PLUGGING.

INVOICED

DATE JUN 01 1993

MAY NO. 32290



J. L. Sanders

(AGENT)